## TABLE 601-xx (native material)

## **MINIMUM TESTING FREQUENCIES**

04/15/21 draft

	ı. n.	/ C•		
Main	lina Pir	oe (fina	l hackti	111
IVIGIII		JC (IIIIa	ı bacıtı	,

Utility Type	Test Area	Minimum Testing Frequency	MAG Section	
		Discussion item: 1 test per lift below subgrade per 500', per 300' (alternate		
Sewer	Final Backfill	between manholes), between each manhole	601	
		1 test per lift below subgrade per 500' (alternate between valves) Discussion item:		
Water	Final Backfill	Between each pipe run	601	
Water Valves	Final Backfill	50% of valves or valve clusters (test 1'-3' away)	601	
		I test per lift per 500' Discussion item: Do we want to combine this with sanitary		
Storm Drain	Final Backfill	sewer testing?	601; 618	
Dry Utilities (PUE)	Final Backfill	I test per lift per 500'	601	

## Services, Laterals, Crossings (final backfill)

Utility Type Test Area Minimum Testing Frequency		Minimum Testing Frequency	MAG Section	
Water, Sewer Services	Final Backfill	25% of services, 1 test per lift below subgrade	601	
Hydrants, Hydrant				
Laterals	Final Backfill	50% of laterals, 1 test per lift below subgrade	601	
Storm Drain Laterals	Final Backfill	50% of laterals, I test per lift below subgrade	601; 718	
Irrigation, Dry Utility				
Crossings	Final Backfill	100% of crossings, 1 test per lift below subgrade	601	

## Structures (foundation, final backfill)

Utility Type Test Area Minimun		Minimum Testing Frequency	MAG Section
Major (Manholes)	Subgrade/ Foundation	1 test per manhole (Cast-In-Place manholes only)	301; 601; Dtls 420, 421
Major (Manholes)	Backfill	1 test per lift per structure, alternate sides of structure	206; 505; 601
Minor (Catch Basins, Headwalls)	Subgrade/ Foundation	50% of structures (for Pre-Cast see ABC Table)	301; 601
Minor (Catch Basins, Headwalls)	Backfill	1 test per lift per structure	206; 505; 601

This Table is for native material. When using ABC, refer to ABC Table 601-xx

(footnote): The Engineer or their representative reserve the right to modify sampling and testing requirements as needed to ensure quality of materials.

(footnote): "Pipe Run" defined as any length of pipe between two consecutive structures along the pipeline. (ie. manholes, fire hydrants, change of directions, or other items)