



TOWN OF BUCKEYE
Engineering Department

Case Number: 13-22

Date : 06-05-13

Revised: 08-21-13

To: MAG Specifications and Details Committee

From: Craig Sharp

RE: Section 625 - Manhole construction and drop sewer connections

Section 775 – Bricks and masonry units

Purpose: Deleting references to bricks and steps in manholes

Revisions:

This revision is to delete references for the use of bricks and steps in sanitary sewer manholes.

SECTION 625

MANHOLE CONSTRUCTION AND DROP SEWER CONNECTIONS

625.1 DESCRIPTION:

625.1.1 Sewer Manholes: Construction shall consist of furnishing all materials and constructing manholes complete in place, as detailed, including foundation walls, ~~cast iron steps~~, manhole frames, covers, and any incidentals thereto, at locations shown on the plans.

625.1.2 Drop Sewer Connections: Construction shall consist of furnishing all materials and constructing drop sewer connections complete in place as detailed, including foundation materials, pipe, and any incidentals thereto, at locations shown on the plans.

625.2 MATERIALS:

Unless otherwise shown on the plans or specified in the special provisions, materials to be used shall conform with the following:

Bricks for manholes ~~Section 775 shall not be used.~~

Cement mortar for manholes Class D, Section [776](#).

Concrete for manholes Class A, for drop sewer connection Class C, Section [725](#).

Pipe used in manholes or drop sewer connections shall comply with pipe requirements of Section [615](#).

Manhole frame, cover ~~and steps~~ Section [787](#) and cast in accordance with standard details.

~~Plastic manhole steps, which conform to O.S.H.A. and A.S.T.M. C 487 requirements, and steel manhole steps, which are completely encapsulated in corrosion resistant rubber and conform to O.S.H.A. and A.S.T.M. C 478 requirements, may be substituted for cast iron manhole steps. The manufacturer shall furnish the Engineer a certification indicating conformance. Manhole steps shall not be used.~~

625.3 CONSTRUCTION METHODS:

625.3.1 Manholes: Manholes shall be constructed ~~of brick~~, of precast concrete sections, ~~or of~~ cast in place concrete, ~~with cast iron manhole steps~~, and frames and covers, in accordance with the standard details. The invert channels shall be smooth and semi-circular in shape, conforming to the inside of the adjacent sewer sections. Changes in direction of flow shall be made with a smooth curve, having a consistent radius as large as the manhole will permit with no angel points. Changes in size and grade of the channels shall be made gradually, ~~and~~ evenly, and uniformly throughout the manhole base.

Invert channels ~~may shall~~ be formed of concrete and or brick masonry ~~having~~ a smooth mortared surface, may be half tile laid in concrete ~~or brick~~, or may be constructed by laying full section of sewer pipe through the manhole and breaking out the top half after the surrounding concrete ~~or brick masonry~~ has hardened. The floor bench of the manhole outside the channels shall be smoothed and shall slope towards the channels.

The excavation shall be in such a manor, access is maintained around the manhole base before, during, and after placement of the manhole. made cylindrical to a diameter sufficient in size to permit sheeting if necessary and leave room that the bricks may be laid in a workmanlike manner and the outside mortar coat properly applied or the precast concrete sections or forms may be properly assembled.

A concrete foundation of Class A concrete shall be poured in accordance with the Standard Details and Section [505](#).

~~Brickwork shall not be laid upon a concrete foundation less than 24 hours after such foundation has been poured. No brickwork shall be laid in water, nor, except as prescribed for curing, shall water be allowed to stand or run on any brickwork until the mortar has thoroughly set. Where new work is joined to existing unfinished work, the contact surfaces of the latter shall be thoroughly cleaned and moistened.~~

SECTION 625

~~Bricks shall be thoroughly moistened prior to placing, and shall be laid in full cement mortar beds. Every course may be a header course, but at least every fourth course shall be a header course. The horizontal cross section of the manhole shall be circular unless otherwise called for on the plans or standard details. An oval or egg shaped section will not be permitted. A double row lock course of brick in the manhole wall shall be arched over the top half of the circumference of all inlet and outlet pipes. The brick manholes shall be mortared outside with ½ inch of cement mortar as shown on the standard details. Inside of brick wall shall be neatly pointed. The mortar coat shall be cured with a liquid membrane forming compound conforming with Section 726 immediately after mortar has been placed and finished.~~

Frame and Cover. All machined surfaces on the frame and cover shall be such that the cover will lie flat in any position in the frame and have a uniform bearing through its entire circumference. Any frame and cover which creates any noise when passed over by automobiles shall be replaced. Frames shall be set firmly in a bed of mortar true to line and grade, all as shown on the plans and as called for in these specifications.

Backfilling shall be done in accordance with the requirements for trench backfilling as stated in Section [601](#).

625.3.2 Drop Sewer Connections: Drop sewer connections shall be constructed in conformance with standard details, as the case may be.

Backfilling shall be done in accordance with the requirements for trench backfilling as stated in Section [601](#).

625.4 MEASUREMENT:

Measurement will be per manhole installed, complete in place, regardless of depth.

625.5 PAYMENT:

Payment will be made at the contract unit price ~~bid~~ for each accepted manhole, and shall be compensation in full for furnishing and installing manhole, complete, with formed or pre-cast inverts, concrete foundation, sanitary sewer drop connections ladder rungs, sheeting and bracing, removal of obstructions cast iron frame and cover, excavation and backfill, paving cut replacement in excess of the applicable pay widths authorized in Section [336](#), and any incidentals thereto, in conformance with the plans and specifications.

~~Payment will be made at the unit price bid each, and shall be compensation in full for furnishing and installing vitrified clay pipe sanitary sewer drop connections, concrete encasement, excavation, backfilling, water settling, compaction, sheeting and bracing, removal of obstructions, paving cut replacement, in excess of the applicable pay widths authorized in Section [336](#), testing, and all work incidental thereto in conformance with the plans and specifications.~~

- End of Section -

SECTION 775

BRICK AND CONCRETE MASONRY UNITS (BLOCKS)

775.1 BRICK:

Brick shall be whole, sound, and hard burned and shall give a clear ringing sound when struck together. They shall be uniform in quality and shall be culled or sorted before delivery to the work.

~~775.1.1 Manhole Brick: Sewer and water manhole b~~Brick shall conform, except for dimensional tolerances, to the requirements of ASTM C32, Grade MM.

~~Manhole b~~Brick shall conform to Table [775-1](#).

TABLE 775-1			
MANHOLE BRICK DIMENSIONS			
Brick	Inches Depth	Inches Width	Inches Length
Standard Size	2 1/4	3 1/2	7 1/2
Allowable Variations	±1/8	±1/8	±1/4

The following paragraphs shall be added to the section on visual inspection:

No individual brick shall be rejected unless it shows visual evidence of major cracking. A major crack is defined as one that has at least one complete separation, for a distance of 1 3/4 inches, through the brick in any direction, including any cored area. Such a crack shall be regarded as affecting the serviceability of the brick and shall be rejected and not used in the structure.

Fifty bricks may be sampled at random intervals from any cube for visual inspection. Of the 50 samples, 45 must pass visual inspection for major cracks. Should less than 45 pass, the cube of brick shall be rejected and the brick must not be used in the structure.

775.1.2 Building Brick: Building brick shall conform to the requirements of ASTM C62, grade MW.

775.1.3 Facing Brick: Facing brick shall conform to the requirements of ASTM C216, Grade MW, Type FBS. The size, color, and texture shall be as specified on the plans or as approved by the Engineer.

775.2 CONCRETE MASONRY UNITS:

Unless otherwise noted on the plans or special provisions, concrete masonry units shall conform to ASTM C90, Normal Weight, Type I with a minimum compressive strength of 1900 psi.

The units shall be fully cured and shall have been made not less than 28 days prior to delivery.

The moisture content at the time of delivery shall not exceed 30 percent of the minimum absorption value of the units. The Contractor shall provide any protection he deems necessary to maintain the units in this condition until time of use.

The linear change from saturated to cool oven dry shall not exceed 0.0054 inches per linear foot or 0.045 of 1 percent conducted in accordance with test method in ASTM C426.

The units shall be made with normal weight aggregate conforming to ASTM C33.

The nominal size of the units shall be as indicated on the plans. The overall dimensions for width, height and length shall differ by not more than ±1/8 inch from the specified standard dimensions. Standard dimensions of units are the manufacturer's designated dimensions. Nominal dimensions of units are equal to the standard dimensions plus the thickness of one mortar joint.

No less than 5 samples of the units shall be submitted to the Engineer for approval and to show the full variance of texture and full range of color. Units used in the work shall match the approved samples. These samples may be tested for strength.

SECTION 775

All units shall be sound and free of cracks or other defects that would interfere with the proper placing of the unit or would significantly impair the strength or permanence of the construction. When units are to be used in an exposed setting, the face or faces that are to be exposed shall not show chips or cracks, not otherwise permitted, or other imperfections when viewed from a distance of not less than 6 feet under diffused lighting.

Units that are intended to serve as a base for plaster or stucco shall have a sufficiently rough surface to afford a good bond.

End of Section -

